



**Request for Bid
Lift Station Rehab Construction Group 1 Addendum No. 1 to
RFB No. 403200.71.0380
March 3, 2020**



The following information encompasses Addendum No. 1 for the above referenced RFB. Bidders shall fully consider and acknowledge this Addendum in the preparation and submittal of its formal Bid. Failure to do so may result in the rejection of the Bid.

Section 1 – Mandatory Pre-Bid Meeting Notes and Questions, Additional Bidder Questions Received to Date, and Sign-In Sheet

Section 2 – Table 00370.3.1 Unit Price Bid Form

Section 3 – Technical Specifications

All other conditions and requirements remain unchanged.

**Section 1
Mandatory Pre-Bid Meeting Notes and Sign-In Sheet**

Q1: Do you have any flow data for the existing lift stations?

SARP10: Draw down tests were performed during each lift station assessment to determine the pumping capacity. The results for the stations included in this project are shown below.

Draw Down Test Results:

3919 North Lakewood

PUMP	PUMP RATE (gpm)
1	37
2	141
Both	130

120 West Industrial Drive

PUMP	PUMP RATE (gpm)
1	0
2	176

4360 Ann Arbor Lane

PUMP	PUMP RATE (gpm)
1	471
2	430



SIGN-IN SHEET

Project: Lift Station Rehab Construction Group 1	Meeting Date: February 25, 2020
Meeting: Prebid Meeting	Time: 9:30 AM
Facilitator: Justin Avent	Place/Room: Benjamin Hooks Library

Name	Company	Phone	E-Mail
Justin Avent	SARP10	901-544-6554	justin.avent@greshamsmith.com
Joe Collins	SARP 10	731-616-8922	Collinsjse@bv.com
Riley Thompson	BU/SARP10	901-495-2649	Thompson LR @bv.com
Wiley Richards	WRT	901-497-1291	wileyrichards@msn.com
Terrell Richards	WRT	901-331-1780	terrellrichards@gmail.com
Kyle Persons	KASACS	573-429-5562	kpersons@kasacs.com
Cain Maynard	Sunbelt Pump	615-838-2954	cain.maynard@sunbeltrentals.com
Josh Wesselmann	Rain For Rent	618-419-5504	jwesselmann@rainforrent.com
Mack Kontemas	LARDMAEK Const	901-277-5045	MAEK@lardmaekco.org
Jahar Conder	Small Business Services	901-318-0590	Office@smallbusinessserv.net
Laurita Jackson	Enfinity Supply	901-219-1468	ljackson@enfinitysupply.co
Darrel Jackson	Enfinity Supply	901-831-9626	djackson@enfinitysupply.com
Troy Reed	CR Coatings	317-710-2144	troy@crcoatings.com
JERRY CALDWELL	Black & Veatch	901-530-1805	caldwellj@bv.com
Michael Gates	Xykm	901-481-1543	michael.gates@xykminc.com
Sosh Grabuski	SARP?	870-574-1719	SGrabuski@worldms.com
James Hink	Magnolia Pms.	901.238.7985	JHink@magmbl.com



Mandatory Pre-Bid Meeting Attendee List



Program: SARP10	Meeting Date: February 25, 2020
Project: Lift Station Rehab Construction Group 1	Time: 9:30 AM
Facilitator: Justin Avent	Place/Room: Benjamin Hooks Public Library

Name	Company	Phone	E-Mail
Justin Avent	SARP10	901-849-6554	justin.avent@greshamsmith.com
Joe J. Collins	SARP10	731-616-8922	collinsjj@bv.com
Riley Thompson	BV / SARP10	901-495-2649	thompsonlr@bv.com
Wiley Richards	W & T Contracting	901-497-1291	wileyrichards@msn.com
Terrell Richards	W&T Contracting	901-331-1780	terrellrichards250@gmail.com
Kyle Persons	KAJACS	573-429-5562	kpersons@kajacs.com
Cain Maynard	Sunbelt	615-838-2854	cain.maynard@sunbeltrentals.com
Josh Wesselmann	Rain for Rent	618-419-5504	jwesselmann@rainforrent.com
Mark Kuntzman	Landmark Construction	901-277-5045	mark@landmarkco.org
Patricia Cordova	Small Business Services	901-348-0590	office@smallbusinessserv.net
Laurita Jackson	Enfinity Supply	901-219-1468	ljackson@enfinitysupply.com
Darryl Jackson	Enfinity Supply	901-831-9626	djackson@enfinitysupply.com
Troy Reed	CTR Coatings	317-710-2144	troy@ctrcoatings.com
Jerry Caldwell	Black & Veatch	901-530-1805	caldwellj@bv.com
Michael Gates	Xylem	901-481-1543	michael.gates@xylem.com
Josh Grabowski	SARP10	870-514-1719	jgrabowski@allworldmail.com
James Hinte	Magnolia Underground	901-238-7985	jhinte@magnoliaunderground.us



**Request for Bid
Lift Station Rehab Construction Group 1 Addendum No. 1 to
RFB No. 403200.71.0380
March 3, 2020**



**Section 2
Table 00370.3.1 Unit Price Bid Form**

Table 00370.3.1 - Unit Price Bid Form

Bidder should refer to Section 00270, Instructions to Bidders, when completing this Bid Form. Bidder shall complete this form entirely and return it with Bidder's Bid.

Bid Submitted by: (Company Name)

00370.3 Bid Pricing Information

00370.3.1 Unit Pricing

Bidder proposes to complete the RFB Work based on firm, fixed, unit prices (US dollars), which prices multiplied by the final Work quantities would represent the full consideration to Bidder for its complete and satisfactory performance of the Work in compliance with all the terms and conditions of the RFB Documents. The Unit Prices in this Table include the cost of all the work which is required or implied by the RFB documents or which may be inferred therefrom, and which is customarily provided in furnishing a complete and finished work item of its kind. Further, any and all alterations, modifications, and adjustments to the work item, which is reasonably foreseeable or customarily encountered in providing and installing equipment, material, and services of the work item kind, will be performed without additional compensation.

In the event of a Purchaser-approved change in the scope of Work for which a unit price from this Table is not applicable, as determined by the Purchaser, the Subcontractor shall provide a new unit price for review and acceptance by the Purchaser. Subcontractor shall provide all information requested by the Purchaser to substantiate the value of the new unit price.

00370.3.1.1 Unit Prices Breakdown **Bidder Response Columns**

Item Number	Item Description	Unit of Measure	Estimated Quantity	Unit Price	Extension Price
71.0380 Lift Station Rehab Construction Group 1					
4360 Ann Arbor Lane					
01551-5.01	Traffic Control Plan	LS	1		\$ -
02630-4.02	Site Preparation and Restoration	LS	1		\$ -
02950-4.01.A-1	Asphaltic Concrete Pavement Removal and Replacement	LS	1		\$ -
02998-4.02	Valve Box with Traffic Rated Cover and Box including Valves, Pipes, Fittings, Support, and any Bypass Pumping as Required	EA	2		\$ -
02999-4.02	Bypass connection Box with Traffic Rated Cover and Box including Plug, Pipes, Fittings, Support, and Bypass Pumping as Required	LS	1		\$ -
09900-4.02	Painting (Wetwell & Drywell, Total Surface Area = 550 square feet)	LS	1		\$ -
09999-3.01	Bollards	EA	3		\$ -
16010-4.01	Demolition of Existing Equipment	LS	1		\$ -
16120-4.01	New Underground 230V Wiring	LS	1		\$ -
16160-4.01	Control Panel with all Equipment, Phase Converter VFD's	LS	1		\$ -
16180-4.01	Pump Motors, Controls, and Wiring	LS	1		\$ -
4360 Ann Arbor Lane - Subtotal Estimated Unit Price Value					\$ -

120 West Industrial Drive

01501-01	Erosion Control	LS	1		\$ -
01501-02	PVC Force Main - 4 inch	LF	300		\$ -
01501-03	Miscellaneous Valves - Bypass Tee Assembly	EA	1		\$ -
01501-04	Wetwell and/or Sewer Manhole Abandonment	EA	1		\$ -
01501-05	Gravel Surface at Pump Station Sites; 6 inch Depth	CY	10		\$ -
01551-6.01	Traffic Control	LS	1		\$ -
02230-01	Clearing and Grubbing	LS	1		\$ -
02530-6.03.15.08.04	8 inch PVC Pipe (14.1' - 18' Deep)	LF	35		\$ -
02530-6.05	Pavement Backfill	CY	60		\$ -
02530-6.06	Bypass Pumping	LS	1		\$ -
02531-4.01.B	Precast Manhole Installation (i.e. Pump Station Wetwell)	VF	21		\$ -
02533-4.01.A	Cementitious Manhole/Wetwell Coating	VF	17		\$ -
02533-4.01.C	Invert and Bench Replacement	EA	1		\$ -
02533-4.01.D	Reset/Reseal Manhole Frame and Cover	EA	1		\$ -
02544-4.01.A	GPS Coordinates of Manhole Cover	EA	2		\$ -
02544-4.01.C-1	MACP Level 2 Manhole Inspections - No 3D Scan	EA	2		\$ -
02630-4.01.A	Site Preparation and Restoration (includes Seeding)	LS	1		\$ -
02631-01	Undercut Backfill	TON	65		\$ -
02820-4.01.A	Chain Link Fence	LF	80		\$ -
02820-4.01.B	Fence Gate	EA	1		\$ -
02950-4.01.A-1	Asphaltic Concrete Pavement Removal and Replacement	SY	80		\$ -

Item Number	Item Description	Unit of Measure	Estimated Quantity	Unit Price	Extension Price
11310-01	Wetwell Mounted Pump Station with Duplex Non-Clog Pumps, including Instrumentation, Controls, and Electrical (Note: includes the flood light and wood pole assembly per Special Conditions 01501)	LS	1		\$ -
120 West Industrial Drive - Subtotal Estimated Unit Price Value					\$ -

3919 North Lakewood Drive					
01501-01	Erosion Control	LS	1		\$ -
01501-03	Miscellaneous Valves - Bypass Tee Assembly	EA	1		\$ -
01501-05	Gravel Surface at Pump Station Sites; 6 inch Depth	CY	12		\$ -
01551-6.01	Traffic Control	LS	1		\$ -
02230-01	Clearing and Grubbing	LS	1		\$ -
02530-6.06	Bypass Pumping	LS	1		\$ -
02533-4.01.A	Cementitious Manhole/Wetwell Coating	VF	23		\$ -
02533-4.01.C	Invert and Bench Replacement	EA	1		\$ -
02544-4.01.A	GPS Coordinates of Manhole Covert	EA	2		\$ -
02544-4.01.C-1	MACP Level 2 Manhole Inspections - No 3D Scan	EA	2		\$ -
02630-4.01.A	Site Preparation and Restoration (includes Seeding)	LS	1		\$ -
02820-4.01.A	Chain Link Fence	LF	70		\$ -
02820-4.01.B	Fence Gate	EA	1		\$ -
11310-01	Wetwell Mounted Pump Station with Duplex Non-Clog Pumps, including Instrumentation, Controls, and Electrical; (Note: includes the flood light and wood pole assembly per Special Conditions 01501, replacement of all piping, bracing, float switches, steps, wall sleeves, etc within the existing wetwell and 5-feet outside wetwell as noted on the plans, and replacement of existing electrical disconnect)	LS	1		\$ -
3919 North Lakewood Drive - Subtotal Estimated Unit Price Value					\$ -

71.0380 Lift Station Rehab Construction Group 1 - TOTAL Estimated Unit Price Value					\$ -
-------------------------------------------------------------------------------------------	--	--	--	--	-------------



**Request for Bid
Lift Station Rehab Construction Group 1 Addendum No. 1 to
RFB No. 403200.71.0380
March 3, 2020**



**Section 3
Technical Specifications**

Along with the strikes noted on the attached page (originally PDF page 164 of the full RFB package), you will also eliminate Section 02544 Manhole GPS & MACP Inspection in it's entirety.

TABLE OF CONTENTS FOR TECHNICAL SPECIFICATIONS

		<u>PAGES</u>
01501	SPECIAL CONDITIONS	1 – 10
01551	TRAFFIC CONTROL FOR CONSTRUCTION WORK ZONES	1 – 6
01610	BASIC PRODUCT REQUIREMENTS	1 – 3
02230	SITE CLEARING	1 – 2
02530	SEWER PIPE INSTALLATION	1 – 29
02531	INSTALLATION AND REPLACEMENT OF MANHOLES AND CONCRETE WETWELLS	1 – 12
02533	REHABILITATION AND REPAIR OF MANHOLES AND WETWELLS	1 – 12
02544	MANHOLE GPS AND MAGP INSPECTION	1 – 9
02630	SITE PREP & RESTORATION	1 – 4
02631	EARTHWORK	1 – 12
02820	CHAIN LINK FENCE	1 – 6
02920	SEEDING	1 – 5
02921	SODDING	1 – 3
02950	REMOVAL AND REPLACEMENT OF PAVEMENTS AND INCIDENTALS	1 – 6
03050	PORTLAND CEMENT CONCRETE	1 – 17
03310	CONCRETE STRUCTURES	1 – 14
11310	WETWELL MOUNTED PUMP STATION	1 – 13

END OF TABLE OF CONTENTS